



**Date:** 10/20/21

**City Project No.:** 20-013

**Addendum No.:** 1

Plan holders:

The following responses to questions received are as follows:

- Q: There is no bid item for 8" SS and 12" SS. Under what bid item should those costs be put?  
A: See change to Section 10.13 of the specifications listed below as Item 1 and attached new Bidding Form (Addendum 01).
- Q: Is the existing section of the road known?  
A: No. Refer to Sections 1.02 and 2.02 of the specifications.
- Q: Sheet 2, note 33 of the General Notes requires a sewer bypass plan. Is this necessary?  
A: Yes. Contractor shall prepare and submit a sewer bypass plan and deploy said plan if necessary.
- Q: For the trench patch steps in Errata 1, can the steps be combined or skipped (particularly step 2) as long as the final trench section is per the detail?  
A: No, Contractor shall follow the steps shown in Errata 1 of the City Standard Specifications.
- Q: There is no pay item for striping. Should the road get re-striped per existing? In what bid item should those costs be put?  
A: See Sections 10.20 through 10.23 of the specification. Contractor shall determine which item(s) to add the costs for this work.
- Q: There is no bid item for loop replacement, but it appears several loops will be lost. Under what bid item should loop replacement be place?  
A: See Section 10.19 of the specifications. Contractor shall determine which item(s) to add the costs for this work.
- Q: Bid item 18 quantity seems to be based on paving back 10' wide. Errata 1 requires paving back at 12'. Can you clarify the trench width? Will the final pay quantity be based on the actual SF paved back?  
A: The quantity under bid item 18 has been revised. See attached new Bidding Form (Addendum 01).
- Q: I was wondering if Golden State Blvd. can be closed down to thru traffic during construction?  
A: No. Contractor shall backfill and utilize traffic plating, as necessary, to provide a safe travel way on all lanes of N Golden State Blvd and shall open the streets to traffic at the end of each work day. Contractor shall maintain access for all adjacent properties along the project site.

The following changes and notations shall be made to the project plans and specifications:

Project Specifications:

**1. Section 10.13 is amended to read as follows:**

**10.13 PVC SANITARY SEWER PIPE:**

Contractor shall install sanitary sewer pipe in accordance with the Standard Specifications and Drawings, the project plans and these special provisions.

Pipe material shall be 18" PVC SDR-35, 12" PVC SDR-26 and 8" PVC SDR-26 sanitary sewer pipe or approved equal. Contractor shall trench in accordance with Standard Specifications including Errata 1, the plans and these special provisions.

Quantities of sanitary sewer pipe to be paid for on the linear foot shall be calculated on the basis of the dimensions shown in the project documents, in the horizontal plane, and adjusted by the amount of any change order by the Engineer. Specifically included in the measurement and payment of 18" PVC SDR-35, 12" PVC SDR-26 and 8" PVC SDR-26 sanitary sewer pipe is the trenching, excavation and replacement of any improvements that are disturbed due to the installation of the pipe.

The contract price paid per linear foot for PVC sanitary sewer pipe shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in constructing and testing the 18" PVC SDR-35, 12" PVC SDR-26 and 8" PVC SDR-26 sanitary sewer pipe, complete in place, as shown on the plans, and as required by law, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer.

If you have any questions, please call me at (209) 668-5599 x4486 or email at [aorosco@turlock.ca.us](mailto:aorosco@turlock.ca.us).

Sincerely,



Anthony R. Orosco, P.E.  
Principal Civil Engineer, Acting City Engineer

Attachments: Bidding Form (Addendum 01)

